BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT38908

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/18/2019-20, Date: 16.11.2019

Improvements of Roads, drains and culverts at Balaji Layout and surrounding area at Kodigehalli ward no 08

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of GANGULU REDDY A ( )		
				In Figures		In Words
1	709.76	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 Page No. 143 / Item No. 19.1, PWD SR 2018-19	Cum	300.0	212928.00	Rupees Three Hundred Only
2	105.87	KSRB 4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (Page No. 13 / Item No. 4.2 PWD SR 2018-19	Cum	5600.0	592872.00	Rupees Five Thousand Six Hundred Only
3	11.88	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 Page No. 25 / Item No. 5.9, PWD SR 2018-19	Cum	6000.0	71280.00	Rupees Six Thousand Only
4	26.19	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. Page No.13, Item No. 4.6 PWD SR 2018-19	Cum	5900.0	154521.00	Rupees Five Thousand Nine Hundred Only
5	19.8	KSRB 15.1.3 Providing ruled pointing 20 mm deep to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications Page No. 115 / Item No. 15.3, PWD SR 2018-19	Sqm	200.0	3960.00	Rupees Two Hundred Only
6	216.09	Providing laying palin / reinforced cement concrete for side drains using M 20 nominal mix concrete with OPC at 300 kgs with 20 mm and down size granite metal course aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed well compacted for walls and bottom including cenmtering shuttering form work etc. complete as per approved drawing and design MORTH Specification No. 1500,1700,2200 Wall & Bottom thickness 15cm Page No. 271, Item No. 37.59.2, PWD SR 2018-19	Cum	7070.0	1527756.30	Rupees Seven Thousand Seventy Only
7	12.97	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 - TMT bars Fe 500 Page No. 18 / Item No. 4.46.2, PWD SR 2018-19	Tonne	75223.0	975642.31	Rupees Seventy Five Thousand Two Hundred Twenty Three Only
8	1524	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete Page No. 27 / Item No. 5.30 PWD SR 2018-19	No	500.0	762000.00	Rupees Five Hundred Only

Signature of the contractor A Ganguly Reddy

30/04

Executive Engineer

30/04

	pproved Qty.	Description	Unit	Approved Tender Rates of GANGULU REDDY A ( )		
				In Figures		In Words
9	308.7	KSRB 15-19.1 : Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. Page No. 124 / Item No. Item No. 15.80, PWD SR 2018-19	Sqm	50.0	15435.00	Rupees Fifty Only
10	308.7	KSRB 15-19.2 : Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications.Page No. 124 / Item No. Item No. 15.81, PWD SR 2018-19	Sqm	120.0	37044.00	Rupees One Hundred Twenty Only
11	20.52	Providing precast slab of 250mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc.,complete as per the direction of engineer in charge - Data rate	Sqm	5700.0	116964.00	Rupees Five Thousand Seven Hundred Only
12	455.4	Providing precast slab of 100mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc.,complete as per the direction of engineer in charge - Data rate	Sqm	2500.0	1138500.00	Rupees Two Thousand Five Hundred Only

A Gangulu Reddy

Signature of the Contractor

30/04

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

30/04